

# SPECIFICATIONS FOR: PRECAST CONCRETE TRUCK PARKING BLOCKS

### **MATERIALS**

Manufactured precast concrete conforming to the following ASTM specifications:

- •Type 1 Portland Cement- ASTM C-150
- Fine and Coarse Aggregate- ASTM C-33
- Steel Reinforcing shall conform to ASTM A-185; A-615
- Steel Anchoring pins conform to ASTM A-185; A-615

## **TECHNICAL DATA**

Nitterhouse Masonry Products, LLC precast concrete wheel stops shall meet the following specifications:

- 5,500 PSI minimum compressive strength
- 6.0% maximum absorption rate
- Steel Reinforced

Finish: High frequency vibration zero slump concrete, Dry Cast-Steel Form Finish

Sizing: 8' L x 12" H x 12" D, 933lbs

#### WARRANTY

Nitterhouse Masonry Products, LLC products are warranted to be manufactured free of defects in workmanship and materials under normal use for a period of one (1) year after date of delivery.

Repair or replacement of defective products at the option of NMP shall be the sole remedy of this warranty.

## MANUFACTURER QUALIFICATIONS

As manufactured by Nitterhouse Masonry Products, LLC 859 Cleveland Ave. Chambersburg, PA 17201

Phone: 717-267-4500

email: masonry@nitterhouse.com www.nitterhousemasonry.com